



SYSTEM SPECIFICATIONS

UPS SYSTEM

PROJECT NAME

CUSTOMER P.O. # - STANDBY ENERGY SEI JOB #

NOMINAL DC BUS SPECIFICATIONS: 105-140 VDC

BATTERY SPECIFICATIONS:

Load Current: 204 ADC, for 4 Hour and 15 Minutes.
Equalize Voltage: 139.2 VDC
Float Voltage: 136.32 VDC
Future Growth: 110%
Aging Factor: 125%

CHARGER SPECIFICATIONS:

Input: 480 VAC, 3 Phase, 60 Hz
Output: 120 VDC, 300 ADC (Nominal)
Current Limit: 120%

NOTE: The maximum Current the charger can provide is 360 ADC. All conductors between the Charger and the Battery must be sized to accept this current.

Float Voltage: 136.32 VDC
Equalize Voltage: 139.2 VDC
Regulation: +/- 0.5%, No Load to Full Load
Ripple: 100 mv

Standby Energy Inc.
14134 Castor Ct.
Tomball, TX 77375
Phone: 281-351-2870



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870

QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |

CUSTOMER:
 PROJECT NAME:

| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------------|-----------|--|-----|------|-------|
| BATTERY UP... | 10 | 120VDC NiCad Battery Saft UP1 L 1400 for a DC Load of 204 ADC, for 4 Hours and 15 Minutes, to an End Voltage of 105 VDC, Floating at 133.4 VDC and Equalizing at 139.2 VDC. 96 CELL SYSTEM (SINGLE CELL BLOCKS) SAFT POCKET PLATE NICKEL CADMIUM CELLS. (FILLED AND CHARGED) 17.2" Deep (across the Rack) and 7.7" Long (down the Rack), 15.9" High, 126 lbs/cell CONFIGURATION: 2 STEP, 2 TIER Battery Hardware: *Inter-cell connectors *Connector Covers *Inter-step cables *Battery end lugs *Adhesive cell numbers *Flame arrestor vent caps *Operating instruction cards *Terminal Protecting Jelly *Terminal Socket | 1 | | |

Blank space for additional notes or terms.

| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------------------|-----------|--|-----|------|-------|
| 2 STEP/2 TIER... | 20 | <p>BATTERY ENCLOSURE & RACK WITH FAN-FAN ALARM, HYDROGEN DETECTOR AND CELL LIFTING SYSTEM</p> <p>*2 Step, 2 Tier Steel Battery Rack (UBC Seismic Zone 2) 3 BOXES EA : 70" L x 48" D x 112" H (not including exhaust fan 24.4") FOR A TOTAL OF: 210" L x 48" D x 112" H *PVC Rack Rail Covers *Lexan Windows (height & width of doors) *Open grate bottom for ventilation *Stove pipe with Cl. 1, Div. 2 Exhaust Fan, Fan Alarm and Hydrogen Detector (24.4" H) - this will have a 90 ° elbow to vent horizontally out of the building. *Cell Lifting System with cell jar brackets that will attach to the hoist hook and connect to the battery lifting handles (as shown on drawing) *Utility grade safety matt 36" x 36" with storage container. *Pad Lockable Door Latches *SS Spill Containment Trays (3 ea) with 24 pillows / tray. *Enclosures will be bolted together at the house builder *Paint: ANSI 61 Gray Powder Coat *NEMA 1 Floor Mount Enclosure</p> | 1 | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|-----------------|-----------|---|-----|------|-------|
| 22kA DCP-1 P... | 30 | 129 VDC DISTRIBUTION PANEL 22kA (all breakers are 2 Pole) 130 VDC, 2 wire 400 ADC CU Bus 1 ea. 400 ADC (Main Chg) Bkr., 2P with tripped alarm contacts 1 ea. 400 ADC (Batt) Bkr., 2P with tripped alarm contact 1 ea 100ADC Bkr, 2P 2 ea. 80 ADC (Inverter) Bkr, 2P 1 ea 60 ADC Bkr, 2P 1 ea. 40 ADC Bkr, 2P 2 ea 30 ADC Bkr, 2P 6 ea 20 ADC Bkr, 2P 1 ea. 15 ADC (BMARS) Bkr., 2P NEMA 1 Wall mount enclosure 24" W x 10" D x 74" H Paint ANSI 61 Gray | 1 | | |
| 300A CHARG... | 40 | A12B-300-130V Features: *INPUT: 480 VAC, 3 Phase, 60 Hz *OUTPUT: 130 VDC, 300 ADC *AC RIPPLE: 100 mv RMS with battery connected. *AUDIBLE NOISE: 65 db @ 5' *REGULATION: ± 0.5% (line, load, temp.) *CURRENT LIMIT: 120% at max voltage (factory set at 115% unless specified) | 1 | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|---|-----|------|-------|
| | | *AC CKT. BKR. 3 Pole, 150 AMPS rms *DC CKT. BKR. 2 Pole, 400 ADC *DIGITAL METER: 2% for VDC, & ADC *FLOAT/EQ. SW. WITH LED'S *FLOAT VOLTAGE SETTING: 133.4 VDC (Field Adjustable TO 145) *AUTO EQ. TIMER BASED ON DC VOLTAGE MODE 4, EQUALIZE DURATION 1-72 HRS *EQUALIZE VOLTAGE SETTING: 139.2 VDC (Field Adjustable TO 148) *HIGH DC SHUTDOWN (SET AT 141VDC) *REVERSE POLARITY PROTECTION *SURGE PROTECTION (INPUT & OUTPUT) *TERMINAL BLOCKS (INPUT & OUTPUT) *INDIVIDUAL ALARM RELAYS AND LED'S for: AC Failure DC Failure High DC at 148 Low DC at 120 VDC and 106 VDC Pos. Ground Neg. Ground High Voltage Shut Down set at 148 VDC COMMON ALARM RELAY *BUILT TO UL 1012 STANDARDS *Wire Markers with Wire Numbers *Remote Equalize Card *INCLUDES OPTION: 21S MODBUS RTU SERIAL DATA PORT RS232/RS485 | | | |




| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|----------|-----------|---|-----|------|-------|
| INVERTER | 50 | *NEMA 1 Floor Mount Enclosure 38" W x 47" D x 72" H, 3400 lbs. *Paint: ANSI 61 GRAY LaMarche Inverter A31-5K-120V-A6 (INVERTER PRIME) La Marche A31 DC/AC Inverter configured with the following features: 5- KVA DC/AC Inverter Internal Inverter/Static Switch/MBP Switch: INVERTER DC INPUT: 105-147 VDC INVERTER DC BREAKER: 80A INVERTER AC BREAKER: 50A BY PASS INPUT TERMINAL BLOCK INVERTER OUTPUT: 120 VAC, 1phase,60Hz T.B. INVERTER OUTPUT REGULATION: 3% over Battery Range INVERTER OUTPUT WAVEFORM: 5% THD, 3% any single harmonic CREST FACTOR for loads up to : 2.8:1 INVERTER PHASE LOCK: Locks to Bypass When the Bypass is 60 Hz ± 0.5 Hz and the slew rate is = 1 Hz/sec. INVERTER INTERNAL OSCILLATOR: 60 Hz ±0.5% INVERTER VOLTAGE TRANSIENT: ±10% for 50% step load change ± 23% for 100% step load change INVERTER RECOVERY TIME: 3 cycles (50 ms for 60 Hz power) | 1 | | |




| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|---|-----|------|-------|
| | | INVERTER OVERLOAD: 500 % for 0.5 Cycle, 130% for 1 min. 125% continuous BYPASS OVERLOAD: 500% for 1 cycle, 150% for 1 minute, 125 % continuous EFFICIENCY: DC/AC 85 - 90% AUDIBLE NOISE: = 70 db on Responsive curve "A" OPERATING TEMP.: 0° C to 50° C STORAGE TEMP.: -20°C to +60° C STATIC SWITCH: 1 Pole, Make Before Break STATIC SWITCH MANUAL TEST SWITCH Rack Mount 75A (MB4B) MANUAL BY PASS SWITCH "Load on AUTO" "Load on Bypass" INSTRUMENTATION: Inverter AC Output Volts 120V NOMIMAL Inverter Output Frequency DIGITAL DISPLAY OPTION 22D UPS AC Output Amps (FLA) 41 ARMS Battery Discharging*LED LOAD ON ALTERNATE SOURCE Bypass Not Available*LED and Relay Inverter/Bypass In Synch. *LED and Relay Static Switch "On Inverter"*LED (LOAD ON PREFERED SOURCE) Static Switch "On Bypass"*LED and Relay (LOAD ON ALTERNATE SOURCE) | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|--|-----|------|-------|
| | | <p>AUTO-START FUNCTION: The UPS includes an auto shutdown and restart circuit. After a loss of AC Power and complete discharge of the battery the unit shuts down. Then when the power returns the UPS automatically restarts the rectifier/charger and after the batteries have recharged to the proper level, approximately 128 VDC, the inverter starts, and picks up the load. Retransfer on loss of Bypass: Electrical Schematic with wire numbers Copy of Test Report</p> <p>THE INVERTER, BYPASS SWITCH AND INVERTER DISTRIBUTION PANEL (IP-01) WILL BE MOUNTED ON A COMMON SEISMIC RATED RACK COMPLETE WITH ALL INTERCONNECTING WIRING AND LIFTING EYES FOR EASY HANDLING 24" W x 19" D x 84" H PAINT: ANSI 61 GRAY POWDER COAT</p> | | | |




| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|-------------|-----------|---|-----|------|-------|
| IP-01 PANEL | 60 | <p>IP-01 PANEL TO MOUNT ABOVE INVERTER AND BYPASS SWITCH 1ea. AC Distribution Panel 30 Circuit, 100 A, 120/240, 1 Ph, 3W, Copper Bus, 22kAIC, 100 A Main Lugs, Top Fed, Surface Mount Distribution Panel</p> <p>List of Materials 1EA:100A, Main Lugs Only 24 EA: Padlockable Lockoff Device 23 EA: 15A, 1P QBHW Branch Breaker 1 EA: 60A, 1P QBHW Branch Breaker 6 EA: 1P QBHW Branch Provision Only 1 EA: Copper Main Bus, 100 Amps 1 EA: Std. Bolted Al Ground Bar (Al/Cu Cable) 1 EA: Panel Nameplate - White with Black Letters 1 EA: Type 1 Enclosure: EZB2036R 1 EA: EZ Trim, Door in Door, Concealed Hardware: EZT2036S NEMA 1 Wall Mount Enclosure 20" W x 6" D x 36" H</p> <p>Will be mounted above the MBP Switch and Inverter on the 23" SEISMIC RATED Relay Rack with lifting eyes for easy handling</p> | 1 | | |




| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------------|-----------|---|-----|------|-------|
| DC/DC CONV... | 70 | (1 EA DUAL 30A SYSTEM) (1 EA DUAL 30A SYSTEM) (1 EA FLOOR MOUNT RACK ASSEMBLY FOR BOTH CONVERTER SYSTEMS) DESCRIBED IN DETAIL BELOW: **DUAL 129/24 VOLT DC/DC CONVERTER SYSTEM: Configured as followed: THESE UNITS ARE MOUNTED IN A NEMA 1 ENCLOSURE WITH SPACE FOR AN ADDITIONAL UNIT ***** ***** (1) DUAL 30A CONVERTER SYSTEM (In same Enclosure) The Enclosure will contain 2 Ea. Converter modules, and 2 Ea. Control Switch Panels to allow Removal of, and Re-installation of any Converter without interrupting power to the 24 VDC Loads. Each Parallel set up is: Configured with 2 ea. Wilmore Model # 1605-130-24-30-MB units: Input: 90-160 VDC, 6.1 ADC DC Input Terminal Block DC Input Circuit Breaker DC Output Terminal Block | 1 | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|---|-----|------|-------|
| | | DC Output VM DC OUTPUT AM Output: 22-26 VDC (adjustable) Factory set at 24 VDC Failure Alarm Relay Contacts, C, NO, NC Eff.:86% Output Regulation:Line +/- 0.1%Load +/- 0.5% Operating temp.: -30 °C to +50°C Storage Temp.: -40°C to + 95°C Current Limit Protection *Blocking Diode Option *Load Sharing Option Relay Rack mount Enclosure 17" W x 13.2" D x 3.45" H The individual converters will be installed and wired to their individual Input and Output DC Switches with adequate cable length to allow the individual converters to be removed from the enclosure prior to disconnecting from their Input and Output Cables. *130 VDC Input Buss (105 – 147 VDC) *24 VDC Output Buss *Output Failure Alarm TB *Load Sharing TB *24 VDC Load Distribution Breakers +/- 24VDC Main Lugs Room for up to 15 ea (2P) Load Breakers (sizes to be determined) | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|--|-----|------|-------|
| | | <p>NEMA 1Wall Mount System Enclosure 22"W x 24"D x 36"H ***** *****</p> <p>**Dual 129/24 VOLT DC/DC CONVERTER SYSTEM Configured as followed: THESE UNITS ARE MOUNTED IN A NEMA 1 ENCLOSURE WITH SPACE FOR AN ADDITIONAL UNIT ***** *****</p> <p>(1) DUAL 30A CONVERTER SYSTEM (In same Enclosure) The Enclosure will contain 2 Ea. Converter modules, and 2 Ea. Control Breaker Panels to allow Removal of, and Re-installation of any Converter without interrupting power to the 24 VDC Loads.</p> <p>Each Parallel set up is: Configured with 2 ea. Wilmore Model # 1605-130-24-30-M3 units: Input: 90-160 VDC, 6.1 ADC DC Input Terminal Block DC Input Circuit Breaker DC Output Terminal Block DC Output VM DC OUTPUT AM</p> | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|---|-----|------|-------|
| | | <p>Output: 22-26 VDC (adjustable) Factory set at 24 VDC Failure Alarm Relay Contacts, C, NO, NC Eff.:86% Output Regulation:Line +/- 0.1%Load +/- 0.5% Operating temp.: -30 °C to +50°C Storage Temp.: -40°C to + 95°C Current Limit Protection *Blocking Diode Option *Load Sharing Option Relay Rack mount Enclosure 17" W x 13.2" D x 3.45" H</p> <p>The individual converters will be installed and wired to their individual Input and Output DC Switches with adequate cable length to allow the individual converters to be removed from the enclosure prior to disconnecting from their Input and Output Cables.</p> <p>*130 VDC Input Buss (105 – 147 VDC) *24 VDC Output Buss *Output Failure Alarm TB *Load Sharing TB *24 VDC Load Distribution Breakers +/- 24VDC Main Lugs</p> <p>Room for up to 15 ea (2P) Load Breakers (sizes to be determined)</p> <p>NEMA 1 Wall Mount System Enclosure 22"W x 24"D x 36"H</p> | | | |




| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------|-----------|---|-----|------|-------|
| BMARS 3 | 80 | <p>***** *****</p> <p>**FLOOR MOUNT RACK ASSEMBLY FOR THE 30A/30A AND 30A/30A DESCRIBED ABOVE 22"W x 28"D x 84"H MUST LEAVE 24' ON LEFT SIDE OF FLOOR MOUNT RACK TO ENABLE IT TO HINGE AWAY FROM BACK PANEL FOR EASY ACCESS</p> <p>BMARS 3 1 ea. Main Control Panel containing: Lexan Back Panel with the following equipment surface mounted on it: 1 ea. Control Tablet 1 ea. Main Control Board 1 ea. Communication Board 1 ea. Interface Board NEMA 1 Fiberglass Wall Mount Enclosure with clear Lexan window in the Latching front door 14" W x 8" D x 16" H</p> <p>20 ea. Monitor Boards and Monitor Cables 1 per 5 cells of the Battery NOTE: All Communication is wireless via XBee control</p> | 1 | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------------|-----------|--|-----|------|-------|
| SAFETY SWL... | 90 | Safety Switch/Fusible Disconnect Switch To Divide the 129V Battery Voltage into 3 equal sections Single Throw –Heavy Duty 2 Pole 400A (BOTH SWITCHES IN ONE ENCLOSURE) Fusible- With No Neutral Supplied with 2 ea 400A fuses and 2 ea spare fuses With tripped Alarm Auxiliary Contact Kit (C,NO, NC) NEMA 1 Wall Mount Enclosure 24" W x 13" D x 45" H | 1 | | |
| APPROVAL D... | 100 | APPROVAL Documentation Provided *One Electronic Copy 3-4 WEEKS ARO *System Interconnect Diagram. *Battery Data Sheet *Battery Interconnect Diagram *Battery IOM *Battery Enclosure Drawing w/ Spill Containment Tray, Cell Lifting Device and Battery Safety Mat *Charger Data Sheet *Charger Outline Drawing | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------------|-----------|--|-----|------|-------|
| FINAL DOCU... | 110 | *Inverter Data Sheet *Static Switch Data Sheet *Manual Maintenance Bypass Switch Data Sheet *Inverter Outline Drawing *Relay Rack Drawing showing Inverter/SS/MBPS and IP-01 Panel Layout Drawing and Dimensions. *DCP-1 Panel Layout Drawing with Dimensions *Battery Safety Switch Data Sheet with Dimensions *DC/DC Converter Data Sheet and Dimensional Drawing *DC/DC Converter Enclosure Dimensional Drawing *24VDC Distribution Breakers *Exhaust Fan and Alarm Data Sheet *Hydrogen Detector Data Sheet *BMARS 3 DESCRIPTION FINAL DOCUMENTATION 1 ea. Digital Copy 3 ea. Hard copies will be mailed as needed *System Interconnect Drawing | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|--|-----|------|-------|
| | | *Charger Data Sheet *Charger Electrical Schematic With Wire Numbers *Charger Outline Drawing *Charger Recommended Spare Parts without Prices *Charger IOM *Charger Test Report *Inverter Data Sheet *Inverter Static Switch Data Sheet *Inverter Manual Maintenance Bypass Switch Data Sheet *Inverter Electrical Schematic With Wire Numbers *Inverter Outline Drawing *Inverter Recommended Spare Parts without Prices *Inverter IOM *Inverter Test Report *Relay Rack Drawing showing Inverter / SS / MBPS and IP-01 Panel with Wiring *IP-01 Panel with Layout Drawing and Dimensions. *Battery Data Sheet *Battery MSDS *Battery Enclosure Drawing w/ Spill | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|------|-----------|--|-----|------|-------|
| | | Containment and Battery Safety Mat *Battery Interconnect Diagram *129 VDC Distribution Panel Dimensional Drawing *129 VDC Distribution Panel Breaker Layout Drawing *Exhaust Fan and Alarm Data Sheet *Hydrogen Detector Data Sheet *BMARS Data Sheet *BMARS Quick Start Guide *Safety Switch Data Sheet *Safety Switch Enclosure Sheet GUARANTEE/WARRANTY: Electronics: Standard Factory Warranty on all electrical and electronics parts. Battery: 5 years full replacement/20 year prorated SHIP TO:TBD SHIPMENT: Batteries 14-16 Wks ARO or 12-14 Wks after | | | |



| |
|--------------|
| TOTAL |
|--------------|



Standby Energy Inc
 14134 Castor St.
 Tomball, TX 77375
 Ph: 281-351-2870


QUOTE

| | |
|------------|---------|
| Date | Quote # |
| 10/1/2020 | XXXXXX |
| REVISION # | 0 |



| | |
|--------------------|----------|
| TERMS | SHIPMENT |
| Progressive/NET 45 | 2021 |

| Item | Line Item | Description | Qty | Each | Total |
|---------------|-----------|---|-----|--------|-------|
| | | Drawing Approval if Approval Drawings are required. | | | |
| | | All other equipment: 8-10 Wks ARO or 6-8 Wks after Drawing Approval if Approval Drawings are required. | | | |
| | | TERMS: Prices good for 90 Days. 20% Net 30 will be Invoiced when the Approval Drawings are submitted. 80% Net 30 Balance will be Invoiced upon shipment of equipment. | | | |
| | | FOB: Factory, PP&A, Freight Collect, or Pick-up | | | |
| PROGRESS P... | 120 | PROGRESS PAYMENT #1: 10% UPON SUBMITTAL OF APPROVAL DRAWINGS | | 10.00% | 0.00 |
| PROGRESS P... | 130 | PROGRESS PAYMENT #2: 10% UPON ACCEPTANCE OF MATERIAL ORDER. | | 10.00% | 0.00 |
| PROGRESS P... | 140 | PROGRESS PAYMENT #3: 80% UPON SHIPMENT | | 80.00% | 0.00 |



| |
|--------------|
| TOTAL |
|--------------|